



BASEMENT FOUNDATION SPECIFICATIONS

Inside Footing and post pads per plans
Outside Footings 20"x8" per state and local codes

8'x8" PCW"

Brick Pattern on Outside

"Windows-vinyl 16"x32" per plan

Anchor Bolts per code

4" Stone under Floor with 6 mil poly

2" Rigid insulation (supplied by owner) beneath basement slab

3" minimum concrete floor graded to proper drainage

Inside & outside drainage- flexible drain tile or form-a-drain with bleeders and connection to sump
crook

Tar Spray

12" stone over outside drain system

Insulation:

Outside 1" rigid insulation supplied by owner placed on foundation before stone.

1" Thermax, supplied by owner, placed inside form on inside of top 2' of forms.

-OR-

Equivalent full-height insulation approved by Habitat

Basement footing to be done within 3 business days of excavation. Foundations to be completed within one week of completion of footings. Some accommodation for weather if approved by Habitat.

Send all bids to:

Milwaukee Habitat for Humanity

3726 N. Booth St

Milwaukee, Wisconsin 53212

Attn: Adam Helt-Baldwin

ahelt@milwaukeehabitat.org

414.562.6100 x17

414.562.4440 Fax
